

05/02/2026

Work Order

To: MJR-Builders Pty Ltd

Order Number: CRA58107-146748

Job Number: CRA58107

Customer Name & Contact Number:	Centacare Evolve Housing . 0409 742 336
Site Address:	48 Tottenham Road, Gagebrook, TAS 7030
Site Contact Phone: (if different to Customer)	
Claim Number:	1949257
Supervisor:	Shane DeWit
Supervisor Email:	shane.dewit@jpflynn.com
Repair Co-ordinator Name:	Tea Iti
Repair Co-ordinator Email:	tea.iti@jpflynn.com
Cause of Damage:	Malicious Damage

Start Date:		Completion Date:	
--------------------	--	-------------------------	--

Special Instructions

Appliances

Kitchen as per scope supplied

Supply and install an in bench 60cm oven, Make: Beko. Model: BBO6850MDX or similar. Confirm the model prior to demolition. PC allowance \$700. (1 unit)

10.19 Supply and install a 60cm cooktop. Make: Beko. Model: Vitro-ceramic 4 Zone Ceramic Cooktop BCT601CG or similar. PC allowance \$400. (1 unit)

10.20 Supply and install an undermount range hood. Make: Beko. Model: BRH52UX or similar. PC allowance \$500.

Blinds / Shutters

Roller blinds

Supply and install retractable roller type blinds to all windows. (10 units)

Builder

External repairs as per scope supplied

Replace windows. As per scope supplied. Allowance for new aluminium sliding sash double glazed windows, with hardwood reveals, as listed. Supply and install powder-coated, aluminium framed, double glazed awning windows and patio door. The 0215 windows are fixed glazed. The remaining awnings. All openable windows are to have insect screens fitted, reveals are Tasmanian Oak. 1/0615, 1/1812, 1/2124D, 1/0912, 2/0215. (6 units)

Supply and install two powder-coated, aluminium framed, double glazed awning windows. All openable windows are to have insect screens fitted, reveals are Tasmanian Oak. 2/2106. (2 units)

Supply and install a powder-coated, aluminium framed, double glazed awning window. All openable windows are to have insect screens fitted, reveals are Tasmanian Oak. 1/1512. (1 unit)

Supply and install a powder-coated, aluminium framed, double glazed awning window with obscure glass. All openable windows are to have insect screens fitted, reveals are Tasmanian Oak. 1/0912.

Replace section of hardwood wall frames. I to Internal and external. Labour and materials.

Replace fire damaged rafters as required. Supply and install new eaves" as per former. Supply and install new soffit framing. Trimmers within 1200mm of external corners to be spaced at 500mm centres. The remainder at to be at max. 700mm centres. Fasteners within 1200mm of external corners to be spaced at 200mm centres, the remainder at 300mm max. centres. (15.6m2. Remove and replace timber roof battens to the affected section of roof frame, allowing for staggering the joints of replacement battens. (24.0m2. Remove and replace the particleboard flooring from the northwestern corner of the living room extending to the patio door. Include any additional blocking at as required. (14.4m2)

)

9.9 Remove and replace the underfloor insulation, 75mm polystyrene, to the extent of flooring replacement. (14.4m2)

)

9.10 Remove and replace the fire damaged wall insulation to the northwestern corner of the room. R2.5. (10.0m2)

)

9.11 With wall linings removed, inspect all wall insulation and wall framing for signs of smoke penetration and replace / encapsulate accordingly. It is assumed that where burn through has not occurred, these material will be undamaged. (1 unit)

)

Replace treated pine back porch, approx size 1.1 x 1.8 meters and stair replacement. Allowance for staircase. x 8 treads. x 1.1 meters wide.

Supply and install a wall mounted light fitting to match the existing to the front entry. (1 unit) 8.20 Deconstruct the front porch roof to facilitate wall frame repair. Allow to reconstruct the front porch on completion. (1 unit) 8.21 Supply and install new H3 treated pine roof battens to the front porch. 3 of x 2.0 linear m (6.0 linear m) 8.22 Supply and install new COLORBOND® corrugated steel roof sheets to the front porch.

Supply and install two soffit vents to the same specification as the existing. (2 units)

Carpentry

Bathroom as per scope supplied

Prepare and paint the door and door jamb using a three-coat interior paint finish. (1 unit)

13.13 Supply and install a PVC door stop. (1 unit)

13.14 Supply and install a 1.02m x 1.02m polymarble shower base. (1 unit)

13.15 Supply and install an aluminium framed pivot shower screen and return panel. (1 unit)

13.16 Supply and install a two wall shower wall system, installed in accordance with the manufacturer installation instructions. (4.4m2)

)

13.17 Supply and install a 900mm wide two door, two drawer vanity unit with moulded top and basin. (1 unit)

13.18 Supply and install a 560mm x 560mm approx. PVC laundry cabinet and sink. (1 unit)

13.19 Supply and install tiled splashbacks to the vanity and laundry cabinet using 600mm x 300mm tiles. 5 tiles. (0.9m2)

)

13.20 Supply and install chrome mixer taps to the laundry trough, vanity unit and shower. (3 units)

13.21 Supply and install a chrome shower rose. (1 unit)

13.22 Supply and basic install chrome washing machine taps. (1 unit)

13.23 Supply and install a ceramic toilet suite. (1 unit)

13.24 Supply and install a chrome toilet roll holder. (1 unit)

13.25 Supply and install a chrome towel ring.

Bedroom 2 as per scope supplied.

Supply and install architraves door and door jamb to best match existing. Approx 10.4lm. Replace Door furniture.

Supply and install skirting to best match existing. Approx 16lm. Replace architraves to window

Dining room as per scope supplied.

Supply and install skirting to best match existing. Approx 6lm.

Kitchen as per scope supplied

Supply and install architraves and door jamb to best match existing. To opening leading to loungeroom

Supply and install skirting to best match existing. Approx 8 lineal meters . Replace architraves. x 6 lineal meters

Loungeroom as per scope supplied.

Supply and install skirting to best match existing. Approx 16lm

Supply and install architraves door and door jamb to best match existing. Replace door furniture

Remove and replace the 190mm x 45mm nominal LVL lintel extending from the southwestern corner along the front entry wall. (3.9 linear m) 9.8 Remove and replace the particleboard flooring from the northwestern corner of the living room extending to the patio door. Include any additional blocking at as required. (14.4m2) 9.9 Remove and replace the underfloor insulation, 75mm polystyrene, to the extent of flooring replacement. (14.4m2) 9.10 Remove and replace the fire damaged wall insulation to the northwestern corner of the room. R2.5. (10.0m2

Supply and install a new rebated timber door frame with sidelight approximately 400mm wide (to suit the existing opening) and solid core door. Include a timber sidelight panel with four glazed sections to match the existing as closely as practicable. Include a deadlock and entrance set, keyed alike.

Master Bedroom as per scope supplied.

Supply and install architraves door and door jamb to best match existing to bedroom doorway. Supply and install new door furniture

Supply and install skirting to best match existing. Approx 14lm. Replace architraves to window

Cleaning

Preliminaries

Allow to leave site clean and tidy. Final clean

Demolition

Preliminaries

Strip out all plaster, joinery trims and fittings to total of unit . Remove damaged roofing . Remove as per scope

Doors

External repairs as per scope supplied

Replace front and back door frames, trims door furniture and external doors x 2 as per closest equivalent .

Floor Sanding/Stripping

Throughout

Allow to sand any peaked joints and remediate any imperfections to the flooring prior to installation of floor coverings. All work is to comply with manufacturer installation instructions and AS1860.2: 2006: Installation of Particleboard Flooring. Throughout unit.

Joinery

Bedroom 2 as per scope supplied.

Supply and install an aluminium framed, vinyl faced two door sliding wardrobe door system to match the existing, approximately 2.1m high x 1.4m wide. (1 unit) 12.16
Supply and install a melamine wardrobe fit out to suit, incorporating a full width shelf and half hanging space with a base shelf and four intermediate shelves.

Dining room as per scope supplied.

Replace built in cupboard

Kitchen as per scope supplied

Replace kitchen in total as per closest equivalent. as follows Supply and install kitchen cabinets comprising an "L" shaped floor mounted unit approximately 3160mm long x 1740mm with oven and cooktop built in. This cabinet is to feature 6 standard doors, one bifold door and 4 drawers. Include a wall mounted overhead cabinet 4 doors. Include a 6 shelf, 2 door pantry 800mm wide, include a fridge cabinet 840mm wide, including 2 overhead doors to match the remainder. Benchtops are rolled edge laminate. Carcases and doors are melamine. (1 unit)

Master Bedroom as per scope supplied.

Supply and install an aluminium framed, vinyl faced two door sliding wardrobe door system to match the existing, approximately 2.1m high x 1.4m wide. (1 unit)
11.16 Supply and install a melamine wardrobe fit out to suit, incorporating a full width shelf and half hanging space with a base shelf and four intermediate shelves.

Painting

Bathroom as per scope supplied

Prepare and paint walls in accordance with paint schedule, inclusive of base coat and two top coats. Approx 23m2

Prepare and paint internal door to best match existing

Prepare and paint ceiling and cornice. Approx area 8m2

Bedroom 2 as per scope supplied.

Prepare and paint walls in accordance with paint schedule, inclusive of base coat and two top coats Approx 31m2

Prepare and paint internal door to best match existing

Prepare and paint skirting and architraves to best match existing

Prepare and paint ceiling and cornice. Approx 11m2

Dining room as per scope supplied.

Prepare and paint walls in accordance with paint schedule, inclusive of base coat and two top coats.

Prepare and paint skirting and architraves to best match existing

Prepare and paint ceiling and cornice.

External repairs as per scope supplied

Prime and repaint external weatherboards and window frames. repaint external doors and door frames. Repaint downpipes. All works as listed in scope supplied.

Clean and encapsulate all exposed ceiling and roof framing, top plates etc exposed to smoke. (94.0m2)

Kitchen as per scope supplied

Prepare and paint walls in accordance with paint schedule, inclusive of base coat and two top coats. Approx 26m2

Prepare and paint two internal door frame and trims to best match existing

Prepare and paint skirting and architraves to best match existing

Prepare and paint ceiling and cornice. approx area 8m2

Loungeroom as per scope supplied.

Prepare and paint walls in accordance with paint schedule, inclusive of base coat and two top coats. Approx area 32m2

Prepare and paint skirting and architraves to best match existing

Prepare and paint one internal door , door frame, to best match existing

Prepare and paint ceiling and cornice.

Master Bedroom as per scope supplied.

Repaint walls as per closest equivalent colour. approx 33m2

Prepare and paint skirting and architraves to best match existing

Prepare and paint internal door and door frame to best match existing and window reveals

Prepare and paint ceiling and cornice.

Plastering

Bathroom as per scope supplied

Supply and install wet area plasterboard, and insulation to walls. set and sand ready for paint. Approx 26m2

Supply and install plasterboard to ceiling and including cornice . Set and sand ready for painting. Approx area 9.2m2

Bedroom 2 as per scope supplied.

Supply and install plasterboard, to ceiling and all walls including insulation to external walls. , set and sand ready for paint. Approx 30 m2

Supply and install plasterboard to ceiling and including cornice and insulation . Set and sand ready for painting. Approx area 11m2

Dining room as per scope supplied.

Supply and install plasterboard, set and sand ready for paint. Approx 8m2 and including walls and insulation

Supply and install plasterboard to ceiling and including cornice . Set and sand ready for painting. Approx area 3m

Kitchen as per scope supplied

Supply and install plasterboard, set and sand ready for paint. To walls including insulation to walls. Approx 26 m2

Supply and install plasterboard to ceiling and including cornice . Set and sand ready for painting. Approx area 10m

Loungeroom as per scope supplied.

Supply and install plasterboard, to wall . set and sand ready for paint. Approx 32m2

Supply and install plasterboard to ceiling and including cornice . Set and sand ready for painting. Approx area 14m2

Master Bedroom as per scope supplied.

Supply and install plasterboard, to walls set and sand ready for paint. Approx 33m2. Insulate external walls

Supply and install plasterboard to ceiling and including cornice and insulation . Set and sand ready for painting. Approx area 14m2.

Roofer

External repairs as per scope supplied

Supply and install new roof cladding and associated blanket , to both units . supply and install associated flashings to chimneys x 2 and to existing roof penetrations. Approx area 97m2. Remove and replace the R4.0 ceiling and roof space insulation batts. (80.0m2)

Remove and replace the COLORBOND® barge flashings. Allow 250G4F. (18.0 linear m)
8.3 Remove and replace the barge flashing at the head of the upper skillion. Allow 270G4F. (11.5 linear m)

Safety/Access Equipment

Preliminaries

Scaffolding. Assembly , hire fees and associated cartage.

Security

Excludes

EXCLUDES temporary monitored security . This will be required in this area.. Estimate of \$6000 based on past repairs in this area.

Monitored security

Allowance for monitored security for duration of repairs.. Allowance for two cameras to external and two cameras fitted internally. Camera's will be linked with mobile phones by means of app.

Skip Bins

Preliminaries

Removal of Debris during construction.

Tarps

Temporary weatherproofing

Additional temporary covering of house during repairs.

Temporary Fencing

Preliminaries

Allowance for temporary fencing during reconstruction.

Tiling

Bathroom as per scope supplied

Supply and install new wall tiling to vanity splashback . Allowance of \$50 per m2 for tile supply. Approx 2m2.

Kitchen as per scope supplied

Supply and install 600mm x 300mm splashback tiles. PC allowance \$55.0/m2
x 2 rows high

Vinyl Flooring

Bathroom as per scope supplied

Supply and install new vinyl and underlay approx area 10m2. Including vinyl skirts.

Kitchen as per scope supplied

Supply and install mid-range vinyl flooring to 3.6m approx. from the end kitchen wall. Ensure floor moisture content is consistent with manufacturer installation recommendations. (13.0m2 Allow to sand any peaked joints and remediate any imperfections to the flooring prior to installation of floor coverings. All work is to comply with manufacturer installation instructions and AS1860.2: 2006: Installation of Particleboard Flooring.

Waterproofing

Bathroom as per scope supplied

Allow for waterproofing as required to floor and shower enclosure

Professional Services

Provisional sums

Power supply for duration of repairs. and temporary toilet and wash facilities.

Totals		Totals
	Subtotal	\$187,500.00
	GST	\$18,750.00
	Total	\$206,250.00

INITIAL CUSTOMER CONTACT:

* You are required to contact the customer within 24 hours of receipt of this work order to arrange a suitable time to attend the property.

UPDATES TO JP FLYNN:

* You are required to advise our office once a date has been arranged with the customer to attend their property as per contractor induction.

* If any variations to the Scope of Works provided are noted whilst on-site, we require you to contact our office for approval prior to proceeding as per contractor induction.

COMMENCEMENT DATE FOR REPAIRS

* We require you to confirm an approximate start date for repairs (including lead times for any materials) as per insurance company requirements.

COMPLETION OF REPAIRS

* We require you to update our office, confirming completion of repairs.

* Please submit your invoice (with an accompanying approval form) within 5 working days on completion of repairs.

ALL INVOICES TO BE SENT TO accounts@jpflynn.com

By accepting this order, you are agreeing to the following terms and conditions;

1. The relationship between you and JP Flynn shall be that of principle and independent contractor and you shall be at liberty to nominate any of your suitably qualified employees or sub-contractors to provide the services, subject to prior agreement with JP Flynn. Any of your employees or subcontractors will be under your sole direction and control and shall not form part of the firm of JP Flynn.
 2. You must comply with all laws and regulations applicable to the operation of your business including, without limitation, legislation in relation to Occupational Health and Safety, Equal Opportunity and Environmental Protection.
 3. You must ensure that your employees and sub-contractors are adequately and regularly trained on matters of occupational health and safety, such training to include any training prescribed by OH&S laws.
 4. You must ensure that appropriate OH&S systems, processes, policies and procedures are in place and predicated to comply with your statutory obligations.
 5. You must ensure that your employees and sub-contractors first assess the safety of providing the Services and that they do not carry out any of the Services if they consider that it is not safe to do so.
 6. A job specific Safe Work Method Statement (SWMS) must be completed prior to any works commencing and must be made available to JP Flynn on request.
 7. You must ensure that all aspects of the Services are performed safely having regard to the health and safety of all persons that may be affected.
 8. You must comply with all Privacy Laws in relation to the Personal Information, whether or not you are an organisation bound by the Privacy Act.
 9. You are required to provide your own skill, transport, tools and management of the service to complete the works at the agreed level of quality and time.
 10. Communication on the status of the job is required and should always reference the JP Flynn Job Number and Purchase Order number.
 11. If JP Flynn deems that any work performed by you, or materials used by you, in providing the Service is defective, JP Flynn may either:
 - a) Require you to rectify the defect at your expense.
 - b) Arrange for another service provider to rectify the defect at your expense.
 12. To the extent permissible by law, JP Flynn is not liable for any death, personal injury or property damage caused by or arising directly or indirectly out of or in connection with:
 - a) Any handling, distribution, storage or use of Hazardous Substances by you.
 - b) Any process of decontamination, treatment, handling, sale, installation, removal, disposal or control of Hazardous Substances by you.
 - c) You failing to adequately assess the safety of performing the service.
 - d) You failing to ensure compliance with all relevant Occupational Health and Safety laws.
 13. You agree to indemnify JP Flynn, and keep JP Flynn indemnified, for any loss or claim suffered or incurred by JP Flynn in connection with or arising directly or indirectly from:
 - a) Any identification, handling, distribution, storage, disposal or use of Hazardous Substances by you.
 - b) Any process of decontamination, treatment, handling, sale, installation, removal, disposal or control of Hazardous Substances by you.
 - c) You failing to adequately assess the safety of performing the service.
 - d) You failing to ensure compliance with all relevant Occupational Health and Safety laws.
 14. You must own and maintain the following insurance policies with reputable insurers and provide certificates of currency upon our request;
 - a) Public and products liability insurance for an amount not less than AUS\$10,000,000 for this and each service and, with respect to products liability, also in aggregate for all claims during any 12 month policy period.
 - b) Workers compensation insurance and registrations as required by law in respect of all persons employed by you to carry out agreed services
 15. The following warranties are implied in the Service provided by you under this agreement:
 - a) A warranty that the Service will be performed in a proper and workmanlike manner and in accordance with the plans and specifications specified.
 - b) A warranty that all materials supplied will be good and suitable for the purpose for which they are used and that, unless otherwise stated, will be new.
 - c) A warranty that the service will be done in accordance with, and will comply with, any other law.
 - d) A warranty that the service will be done with due diligence and within the time stipulated.
 - e) A warranty that the Service and any materials used in carrying out the Service will be reasonably fit for the specified purpose or result.
 16. On completion of the agreed works a tax invoice must be issued to JP Flynn within 5 working days for payment
- The tax invoice must include:
- a) JP Flynn Job Number.
 - b) JP Flynn Work Order Number.
 - c) Your Job Number (If Applicable).



- d) Customer Name and Address.
- e) A signed Customer Approval Form (Available at www.jpflynn.com).
- f) Itemised description of labour (hours) and materials (dollar amount) supplied.
- g) Costs should be stated as price excluding GST, the GST component, and the total cost.